

## The Main Loop

Lay out the Main Loop with the Layout Stick (5 1/2" from the back).  
Pull the Main Loop with the backing on, starting in the cellar and with no twists or splices (one continuous piece).  
Lay the Main Loop starting at the end and pulling extra Tapewire into the cellar; removing enough backing to get well into the next floor, then pull the extra material back and rub down the tapewire

on the Foundation. In the first floor, pull extra tapewire from the floor above and remove enough backing to rub down the tapewire in the first floor plus a bit more. Pull the extra back and rub it down. Continue in this manner to lay the tapewire for the whole house

